



Weed Control Plan

Kerr McGee Gathering LLC commits to the following weed control Best Management Practices during and after the construction of the Conoco Mustang Pipeline:

- All equipment will be clean when arriving to site to prevent the spread of noxious or invasive species.
- Kerr McGee Gathering LLC will practice weed suppression by requiring contractor's equipment to be washed and free of dirt and vegetation prior to mobilization to the route.
- Sediment control logs shall consist of straw, compost, excelsior or coconut fiber, and shall be free of any noxious weed seeds or defects including rips, holes and obvious wear.
- After construction, we will use weed free straw to crimp the Right of Way to help allow for absorption during rain events and prevent erosion.
- The route will be maintained per landowner agreements to prevent the spread of noxious weeds.
- If weeds occur, then we frequently send out mowing crews to keep the weeds down.
- Minimizing the disturbed areas on the route at any given time should prevent windborne weed seeds from being introduced.