MAZZETTI

Fill in shaded cells

Bellco Airport and Alameda — Project Number 0210253.01

PLUMBING FIXTURE UNITS — By SR

OFFICES — Date 7/30/21 — Page 1

1

MARK	FIXTURE TYPE	QTY	WSFU[1] EACH	WSFU TOTAL	CW FU[2] EACH	CW FU TOTAL	HW FU[2] EACH	HW FU TOTAL	HW GPH EACH	HW GPH TOTAL	SEWER FU EACH	SEWER FU TOTAL
P1	WC - FT - PUBLIC	2	2.5	5.0	2.50	5.00	-	-	-	-	4	8
P2	LAVATORY - PUBLIC	2	1.0	2.0	0.75	1.50	0.75	1.50	2	4	1	2
P3	SINK - DOUBLE	1	2.0	2.0	1.50	1.50	1.50	1.50	10	10	3	3
P4	SINK - MOP/SERVICE	1	3.0	3.0	2.25	2.25	2.25	2.25	10	10	3	3
P5	DISHWASHER	1	1.5	1.5	-	-	1.50	1.50	15	15	2	2
P6	DF / EWC	1	1.0	1.0	1.00	1.00	-	-	-	-	1	1
TOTALS				**15**		**11.25**		**6.75**		**39**		**19**

1.

2.